



205 E. 28th St. <77803>
P.O. Box 1000
Bryan, TX 77805
Phone: 979-821-5860
FAX: 979-821-5795
<http://www.btutilities.com>

ADDENDUM No. 1
Date: June 26, 2009

Addendum to our Bid Request No. 082-09-09
Finfeather from Cottage Grove to Palasota

Please be advised of the following changes to the bid request package referenced above:

Please replace page 37 of 37 with the attached page. This page has been revised.

We regret any inconvenience this change may cause you in processing this bid request. If you should have any questions please call me at (979) 821-5860.

Sincerely,

Phebe Mosley
Procurement Specialist

Proposal

The undersigned proposes to perform the materials construction in the quantities requested by Owner throughout the duration of this contract.

Bid Price

The conductor install price shall include leaving the existing circuits energized during construction, all temporary jumpers for all existing equipment and services and their cutover to the new conductor. Closing jumpers at all dead-ends, spreading existing conductors and removal of all temporary spreader arms and/or any other temporary devices used during construction. All existing framing shall be left as is, including all dead-ends and double dead-ends.

UPGRADE CONDUCTOR ON FINFEATHER

INSTALL				
UNIT #	UNIT DESCRIPTION	QUANTITY	UNIT PRICE	EXTENDED PRICE
1	Install 477AACB three phase primary double circuit, includes sagging, dead-ending and tying in, per foot.	29,520'		
2	Install 4/0 ACSR neutral, includes sagging, dead-ending and tying in, per foot.	4,700'		
3	Pole #23 – cut double dead-end in neutral and tie existing neutral to new.	1		
4	Install C8 one pole north of #24 on top circuit. New primary on top circuit will dead-end here with existing 4/0 primary to the north remaining.	1		
SUB-TOTAL FOR INSTALLS =				\$
REMOVAL				
UNIT #	UNIT DESCRIPTION	QUANTITY	UNIT PRICE	EXTENDED PRICE
1	Remove 2/0 copper three phase primary double circuit and return to BTU warehouse, per foot.	24,200'		
2	Remove #2 copper stranded neutral and return to BTU warehouse, per foot.	9,500'		
3	Remove 4/0 ACSR three phase primary and return to BTU warehouse, per foot.	2,800'		
SUB-TOTAL FOR REMOVALS =				\$

Description	Total
TOTAL BID AMOUNT	\$

Deleted:
Deleted: ... [2]

A) It is understood the Contractor is responsible for ensuring that any existing utilities are properly located prior to digging and shall make a reasonable effort not to damage any existing utilities. All locating expenses shall be included in the unit prices.

Formatted: Default Paragraph Font, Font: (Default) Arial, 8 pt
Deleted: 52